



GERCKEN COMPANY LLC.

137 N STEWART RD Suite 100 LIBERTY MO 64068

816-781-7491 Fax 816-781-7496

Ric's Cell 816-668-6806 Email Ric@gerckenconstruction.com



Thank you for inquiring about the **MASTER REMODEL** work that we discussed. I have written the following proposal in an outlined manner, showing the phases of work and what is included in each phase. Please review to confirm that I have proposed what you would like to have done.

1. Demolition:

- Remove the countertop.
- Take down 2 sink lights and 2 mirrors.
- Extract 2 vanities and 2 toilets (master bath and hall bath).
- Demolish the shower door.
- Remove baseboard.
- Eliminate shower tile and base, tub ceramic tile, and ceramic flooring.

2. Framing:

- Construct a corner shelf.
- Install a G2 Niche.

3. Plumbing:

- Install a new free-standing tub.
- Set up a shower faucet.
- Add a floor-mounted tub filler.
- Include a handheld shower.

4. Electrical:

- Cap the whirlpool tub.

5. Drywall:

- Perform wall patching.

6. Millwork & Trim:

- Reinstall and supply missing baseboard.

7. Fixtures & Finishes:

- Install new Tiffany shower components.

- Lay down LVT flooring.
- Reinstall sink faucets.
- Set up 2 vanities with 2 Tiffany sink tops.
- Install 2 new sink lights.
- Replace 2 toilets.
- Hang 2 mirrors.

8. Clean:

- Thoroughly clean up the project site and dispose of construction debris.

Preliminary Requirements

Permits & Licenses

Permit(s) by GCS- We will apply for a building permit from the administrative authorities and accommodate the rough-in and final inspections. *The cost of the permits vary, as such, we will bill at our cost for the permit and related fees in addition to this proposal. Surveying, planning & zoning meetings, engineering or other related services if required are available optionally*

Site Prep

Personal Contents: Please remove your personal contents from the work area and protect the same during the project. Where applicable, remove contents from cabinetry, wall hung items from both sides of the walls related to the work area, furnishings, blinds, shades and remove other items that may be subject to damage.

Floor Protection- GCS will supply and install carpet masking or floor covering from our access point to the work area. Note: GCS liability resulting from floor protection or carpet masking installation shall be limited to the cost of providing carpet cleaning should adhesive issues occur, or \$500.00 whichever is less.

Demolition

Cabinet & Tops Demolition

Countertop Removal- Remove the existing vanity counter tops

Plumbing Demolition

Water Line Disconnect- cut and cap off 1/2" water supply. Includes shut-off and drain down and pressure test.

Drain Line Disconnect- Cut and cap off drain 1 1/2" or 2" drain, waste and vent piping.

Water Shut-Off(s)- Some existing fixture water shut-offs are found to be leaking when the water supply line is disconnected indicating a need for replacement. Replacement shut-offs, installed in place of existing will cost \$39.00 each labor and materials.

Bathroom Surface Mounted Fixture & Hardware Removal

Sink Light(s)- Remove and discard

Mirror(s)- Remove and discard

Towel Bars- Stays intact

Toilet Paper Rack- Stays intact

Sink Faucet(s)- Shut off the existing water stops and disconnect the faucet supply lines. Dismount from the sink or sink top.

Vanity- Remove the existing vanity.

Stool: Disconnect Master Toilet and Hall Toilet, detach and remove the stools- **Discard**

Shower Door/Enclosure: Remove the existing shower door and **discard**.

Exhaust Fan- **None- Stays intact**

Millwork-Doors & Trim Removal

Baseboard-Remove the existing baseboard and salvage (if applicable) for re-installation.

Bathroom Surfaces Removal

Shower Ceramic Tile: Remove the ceramic tile and attached wallboard from the existing tub or tub/shower to expose framing.

Tub Wall Tile- Remove the existing tile and backing board to expose the framed wall.

Shower and Bathroom Wall Tile- Remove the existing tile and backing board to expose the framed wall.

Bathroom Built-in Fixtures Removal

Shower Faucet: Remove the existing faucet and cap off water lines or prep for new faucet

Shower Base-Fiberglass: Remove the existing shower base and disconnect the drain.

Whirlpool Tub Deck Faucet- Remove the accessible tub deck faucet and cap off the water lines.

Whirlpool Tub Removal- Detach the water supply lines and cap off, detach the drain, remove the tub unit and discard.

Whirlpool Tub Enclosure Removal- Dismantle and remove the whirlpool tub enclosure to expose the sub floor and framed wall.

Whirlpool Tub Skirting (Face)- Remove the existing face enclosure from the whirlpool tub.

HVAC Demolition

None- Duct work demolition has not been anticipated or proposed.

Flooring Removal

Ceramic Flooring: Remove the existing flooring and expose the sub floor. Haul debris from premise.

Bathroom Framing

If needed Grab Bar, Towel Bar, Accessory and Holder Blocking, (Already Exposed Framing): When the fixture location is determined ahead of time and if the wall framing cavities are exposed, we will install wood blocking to mount the towel bar(s), Grab Bar(s) or accessories. Price per each. May require demolition and drywall work to be added if wallboard removal is not proposed otherwise.

Corner Shelf: Fabricate a corner shelf. See Floor plan for details

Windows

None: Window removal, replacement or modification has not been proposed.

Plumbing-Rough in

Shower

Tub Fixture

Free Standing Tub- Install the waste and overflow to the free-standing tub unit and set into position. Connect the trap and drain. Set the tub and shell into position and secure.

Water Supply Piping and Fixtures

Shower Faucet: Mount the valve assembly, shower head adapter and connect to the water piping. Install trim kit to include the valve core, handle(s), cover plate, and shower head.

Floor Mounted Tub Filler Faucet- Extend the underfloor water piping to the proposed location. Install faucet mounting plate/bracket, stub for setting of the faucet after finished flooring is installed.

Handheld Shower Assembly- Mount holder bracket and connect a handheld shower sprayer hose to the proposed valve.

Electrical Rough-in

None Proposed- Electrical rough-in modifications have not been proposed

Insulation

Wall- Fill Voids- If wall insulation is disrupted during construction, we will reset the original or if unavailable, obtain and install new insulation to the exposed exterior wall cavity voids.

Drywall

Wall Patch- Install sheetrock and finish smooth to the adjoining wall surface. Sand, ready for primer

Drywall Texture Finish

None- Ceiling or wall texture has not been proposed

Cabinets & Vanity's

Vanity(s)- Provide the labor to set and secure pre-assembled floor mounted vanity. Installation includes cutting holes for the water supply and drain piping. Depending on the configuration of the vanity, cabinet modification or relocation of the piping may be required. If so, additional labor and cost may be required.

Sink Top(s)

Set Sink Top- Set and secure a sink top to the existing vanity. To include side and back splash blocks (if included) **Note:** This applies to premanufactured tops including sink bowl(s). If top modification, fabrication, assembly and or sink setting and attachment are required, an additional charge will apply.

Millwork- Doors & Trim

Baseboard Supply New- Provide standard colonial pattern, ranch or 1x baseboard to the walls where the existing is disrupted or new proposed.

Baseboard Reinstallation- Reinstall the original baseboard to the existing walls.

Tiffany Shower Components

Wall Panel Installation- Install the custom sized Tiffany wall panels. Apply mastic, cut, fit and hang the wall panels proposed

Wall Panel Trim- Install the Tiffany corner molding

Wall Niche- Install the Tiffany recessed wall Niche, into an available existing framed wall cavity, cut the opening in the targeted location

Corner Tub Shelf- Mount the premanufactured Tiffany corner shelf(ves) unit

Shower Base- Set and connect the proposed Tiffany shower base

Flooring

Laminate Interlocking Flooring- We will provide the labor and fasteners to cut, fit and fasten into position the wood or composite interlocking flooring to the designated areas.

Painting

None Proposed- Painting, preparation, sanding, nail hole filling, caulking, spackling, staining of cabinets, trim or other finishing work has not been proposed. When painting work is not included in GCS proposal, it should be done as not to interfere with the completion of work in this proposal. Painting of the sink wall and behind the toilet can be done (by others) while we are completing our work. (Pre-painting the sink wall and toilet wall will allow the painting after we are complete) The painter can either come during the evening after our workday or once we are completed. If the project is stopped for work to be done by others, a remobilization fee will be charged.

Finish Plumbing

Sink Faucet: Provide the labor and plumbing fittings to install 2 sink faucet and pop-up drain

Vanity: Install a ready fit vanity and fasten in place. Cut holes for piping when encountered.

Shower Faucet Trim Installation- Install the shower trim, including the handle, escutcheons and shower head.

Toilet Installation for Master Bath & Hall Bath.: Provide the labor to install a standard floor mounted stool to an existing stool flange, set and connect the provided water supply line and stool seat. Note: some toilets require servicing of tank seals or other components. Rebuilding or servicing of your original toilet may exceed the value of the used toilet. The cost of repairing an existing stool has not been included in this proposal.

Finish Electrical- Fixture and Device Mounting- Installation labor

Sink Light Fixtures- Install the surface mounted fixture compatible with the existing electrical box and wiring.

Hardware Installation

None- Hardware modification or installation has not been proposed.

Shower Enclosure's & Doors

Shower Door & Enclosure by Glass Shop- Provided and installed by others, has not been proposed

Mirror(s)

Mirror- Install the surface mounted mirror. Place anchors or screws at the mirror mounting points.

Job Clean Up & Disposal

Pick-up Truck Hauling- Per bed of truck hauled to our dumpster approx. 2.5 yards or 1/2 ton load whichever is applicable. This is to remove the ongoing debris after the initial demolition dump bed trailer is removed.

Clean Up: Remove all construction debris from the job site, sweep the floor and clean the work area upon completion. Other cleaning has not been proposed.

**TOTAL ESTIMATED CONTRACTOR'S WORK FOR
BATHROOM PROJECT AS LISTED ABOVE:
\$19,668.00 - \$27,043.00**

Bathroom Fixtures and Finishes Purchasing Guide

This is a list of the **Owner Selected & Provided Items**. To accommodate the variety of selections for the Bathroom components, we are inserting minimum estimated valuations for each of the below listed components. Upon making your final selections, please purchase the items and arrange for delivery to the job site, or optionally ask that GCS add these to our contract at an additional charge. The cost of the Fixtures & Finishes is separate from the Contractors Work listed in the Project Proposal. The dollar amounts shown are examples. Your final selections may be more or less. It is your choice what fixtures and finishes you select and the price you pay. Please use the following as an aid for your selection and shopping purposes. Note: Actual quantities may vary.

Desc	Product	Notes	Unit of Measure	Purchase Qty	Estimated Cost Ea.	Total Cost Est
Sink						
Vanity	Vanity	Pre manufactured	Ea.	2	499.00	998.00
Mirror		Surface Mounted	Ea.	2	49.00	98.00
Sink Faucet(s)			Ea.	2		
Sink Light Fixture(s)			Ea.	2	49.00	98.00
Bath Tub						
Free Standing Tub				1	799.00	799.00
Floor Mount Tub Faucet				1	299.00	299.00
Shower Faucet & Handheld	Shower Faucet	Includes the valve body and trim kit. Tub/Shower faucets can be used for shower only	Ea.	1	199.00	199.00
Glass & Glazing						
Custom Glass Door (6'6" clear entrance)	Glass Entry Door	Provided by glass shop. They will measure once the tile is in place and install the door. See vendor referral list for available shops.	Ea.	1	1199.00	1199.00
Flooring						
Laminate Flooring		Interlocking flooring, including transitions, and backing if any.	Sq Ft	170	3.29	559.30
Toilet						
Toilet		Per your selection	Ea.	2	199.00	398.00
Bathroom Fixtures & Finishes estimated before tax					\$	4,647.30

Note: You will pay directly to the supplying vendor. These items are not supplied by GCS, handled or marked up. You pay the direct purchase price, which saves you money!

Financial Consideration- Whatever your financial needs are, we have a solution to get your project started! Just let us know how we can help.

Project Commencement- We typically run approximately 6 weeks for new project startups. The actual completion time will vary with the details and extent specific to your project.

Thanks again for inviting us to provide this information. We look forward to working on and completing your **Master Bathroom** remodel project.

SINCERELY

Alejandro Franco

ALEJANDRO FRANCO
Sales Representative
GERCKEN CONSTRUCTION SERVICES LLC.
A dba of GERCKEN COMPANY LLC.

